




## Maximum Load Test Results

**180 Day Cure Time**

### SB-190 ADHESIVE MOUNTED SNOBLOX DEUCE




**Test Results**  
Peak Load: 1379,2000 lbf

**Deuce 1379.2 Lbs.**

#### Test Summary

Counter: 15046  
Elapsed Time: 00:01:32  
ATI #: 01-43375  
Client: Snoblox  
Material Type: Deuce SB-190 Clear  
Sample #: 2  
Comments:  
Procedure Name: Snoblox  
Start Date: 12/16/02  
Start Time: 11:37:57 AM  
End Date: 12/16/02  
End Time: 11:39:29 AM  
Workstation: Architectural Testing Inc.  
Tested By: Rodney

### SB-190 ADHESIVE MOUNTED SNOBLOX ACE




**Test Results**  
Peak Load: 1449,1000 lbf

**Ace 1449.1 Lbs.**

#### Test Summary

Counter: 15049  
Elapsed Time: 00:02:23  
ATI #: 01-43375  
Client: Snoblox  
Material Type: Ace - SB 190 Clear  
Sample #: 1  
Comments: Phase 3  
Procedure Name: Snoblox  
Start Date: 12/16/02  
Start Time: 11:53:05 AM  
End Date: 12/16/02  
End Time: 11:55:28 AM  
Workstation: Architectural Testing Inc.  
Tested By: Rodney

### 3 - SCREWS MOUNTED SNOBLOX DEUCE




**Test Results**  
Peak Load: 3456,7000 lbf

**Deuce 3456.7 Lbs.**

#### Test Summary

Counter: 15055  
Elapsed Time: 00:04:24  
ATI #: 01-43375  
Client: Snoblox  
Material Type: Deuce - 3 #14 Screws  
Sample #: 1  
Comments:  
Procedure Name: Snoblox  
Start Date: 12/16/02  
Start Time: 12:34:11 PM  
End Date: 12/16/02  
End Time: 12:38:35 PM  
Workstation: Architectural Testing Inc.  
Tested By: Rodney

### 4 - SCREWS MOUNTED SNOBLOX ACE



**Test Results**  
Peak Load: 4849,9000 lbf

**Ace 4849.9 Lbs.**

#### Test Summary

Counter: 15054  
Elapsed Time: 00:04:14  
ATI #: 01-43375  
Client: Snoblox  
Material Type: Ace - 4 #14 Screws  
Sample #: 1  
Comments: Phase 3  
Procedure Name: Snoblox  
Start Date: 12/16/02  
Start Time: 12:23:21 PM  
End Date: 12/16/02  
End Time: 12:27:35 PM  
Workstation: Architectural Testing Inc.  
Tested By: Rodney




Maximum Load Test Results

180 Day Cure Time


SB 190 ADHESIVE MOUNTED ICEJAX I

SB 190 ADHESIVE MOUNTED ICEJAX II



Test Results  
Peak Load: 500.6000 lbf

ICEJAX I  
500.6 lbs



Test Results  
Peak Load: 1561.5000 lbf


ICEJAX II  
1561.5 lbs

**Test Summary**  
Counter: 39993  
Elapsed Time: 00:01:41  
ATI #: 01-99999  
Client: Snoblox  
Material Type: Surebond 190 ICEJAX I  
Sample #: 3  
Comments:  
Procedure Name: Snoblox  
Start Date: 12/8/05  
Start Time: 9:57:06 AM  
End Date: 12/8/05  
End Time: 9:58:47 AM  
Workstation: Architectural Testing Inc.  
Tested By: TODD  
Load Cell: 50K  
Rate of Test: 0.125 in/min.

**Test Summary**  
Counter: 39997  
Elapsed Time: 00:02:49  
ATI #: 01-99999  
Client: Snoblox  
Material Type: Surebond 190 ICEJAX II  
Sample #: 3  
Comments:  
Procedure Name: Snoblox  
Start Date: 12/8/05  
Start Time: 10:28:07 AM  
End Date: 12/8/05  
End Time: 10:30:56 AM  
Workstation: Architectural Testing Inc.  
Tested By: TODD  
Load Cell: 50K  
Rate of Test: 0.125 in/min.


4-SCREWS MOUNTED ICEJAX I

4-SCREWS MOUNTED ICEJAX II



Test Results  
Peak Load: 4213.1000 lbf

ICEJAX I  
4213.1 lbs



Test Results  
Peak Load: 6388.1000 lbf

ICEJAX II  
6388.1 lbs

**Test Summary**  
Counter: 39994  
Elapsed Time: 00:06:04  
ATI #: 01-99999  
Client: Snoblox  
Material Type: ICEJAX I  
Sample #: 4 - with screws  
Comments: #14 Self-T SS  
Procedure Name: Snoblox  
Start Date: 12/8/05  
Start Time: 10:05:27 AM  
End Date: 12/8/05  
End Time: 10:11:31 AM  
Workstation: Architectural Testing Inc.  
Tested By: TODD  
Load Cell: 50K  
Rate of Test: 0.125 in/min.

**Test Summary**  
Counter: 39998  
Elapsed Time: 00:09:00  
ATI #: 01-99999  
Client: Snoblox  
Material Type: ICEJAX II  
Sample #: 4 - with screws  
Comments: #14 Self-T SS  
Procedure Name: Snoblox  
Start Date: 12/8/05  
Start Time: 10:35:25 AM  
End Date: 12/8/05  
End Time: 10:44:25 AM  
Workstation: Architectural Testing Inc.  
Tested By: TODD  
Load Cell: 50K  
Rate of Test: 0.125 in/min.